

GUIDELINES FOR STAND BUILDING



PU TECH 2022

Polyurethane Exhibition & Conference - India

23 - 25 Mar 2022, India Expo Centre, Greater Noida, New Delhi

IMPORTANT INFO ABOUT BUILDING YOUR STAND AT PU TECH 2022



**NO METAL
WELDING**



**NO SPRAY
PAINTING**



**NO WOOD BOARD
SANDING**



**NO WOOD BOARD
CUTTING**



**KEEP WORK
SITE CLEAN**

USE OF PREFABRICATED, PRE-FINISHED, READY TO FIX, MODULAR STAND BUILDING ONLY

ANY VIOLATION, WORK WILL BE ASKED TO STOP

Guidelines for Stand Building

Exhibitors can appoint a contractor of their choice for Stand design and Stand construction. Stand building schedule is as follows:

Type of Stand	Date & Time Start	End Date & Time
Set Up (Raw Space)	21 March 2022 (Mon) 10.00	nonstop until 22 March 2022 (Tue) 20.00 hrs
Set Up (Built up)	22 March 2022 (Tue) 10.00	nonstop until 22 March 2022 (Tue) 20.00 hrs
Dismantle (Raw / Bare)	25 March 2022 (Fri) 5.00 PM	25 March 2022 (Fri) Midnight

For Raw Space exhibitors, organizers will allot only bare space with proper marking of the borders on the floor for the area booked. Construction of partition walls is the responsibility of the raw space Stand holder.

Raw space Exhibitors are required to submit Stand design, elevation and 3D artist's impression, for its approval positively before 31st January 2022. An exhibitor, whose design has been approved by the organisers, can commence erection after taking official possession of the Stand area.

Please Note: Stand height in Halls should not exceed more than 2.5 meters for shell scheme / 4 meters for raw space.

However, the back wall of the Stand against natural wall of the hall or column can go up to a height of 5 meters. Pillars within the Stands should be covered with panelling up to height of 5.0 meters without grouting on the wall, floor or causing damage to the structure of the exhibition hall. A door / window should be provided on such panelling, in case the pillar has electrical supply point / distribution boards for access. Logos and single branding signage up to a height of 5.0 meters is allowed, provided they are away from adjacent Stands by a minimum distance of 2 meters.

NO CUTTING OF WOODEN BOARDS / PLYWOOD / MDF IS PERMITTED INSIDE THE HALLS DURING STAND BUILD UP.

NO SPRAY PAINTING ALLOWED INSIDE THE HALLS DURING STAND BUILD UP.

NO WELDING OR METAL GRINDING ALLOWED DURING STAND BUILD UP.

Any exhibitor or contractor violating the above will be asked to stop the work immediately. We strongly advise contractors to use prefinished, prefabricated, ready to fix, modular Stand building techniques.

Aisles in the halls must be kept clear even during the construction and dismantling periods since they are required as rescue and escape routes. Construction material, garbage, empty packaging and exhibits are not allowed to be kept in the aisles at any time.

Use this guideline for your stand design and building. Mail copy of this document to your stand contractor.
For any clarification, contact Event Managers, Unitech Exhibitions Pvt Ltd,
Ms. Reena +91 9500076535 or reena@unitechexpo.com

Exhibitors should leave minimum 30% of the Stand area free for movement of visitors. There should be no loose wiring or hanging wires within your stand. All wiring must be carried out in plastic sheathed cables. No exposed cable joints are permitted. The main supply points and electrical installations in the Stand should be easily accessible and should not be concealed /covered by the panels / partitions or even by the exhibits.

Sides, which are open to the aisles and more than 6 m in length, should not be blocked by panels more than 50% of the length of such side.

The panels adjacent to other stand areas that are visible must be properly finished in neutral colour without any graphics.

Digging, grouting or cutting of floor is strictly not permitted in halls.

Use of loudspeakers, musical instruments etc. in the Stands is prohibited. Films and multimedia presentations may however be conducted within the Stands provided the sound level is not more than 60 decibels, measured at the Stand limits.

Cellulose paints should not be sprayed on any type of object within the Exhibition Halls. Use of exhibit materials that are dangerous, inflammable, explosive, unhealthy, foul-smelling is not permitted.

Use of coloured lights, neon signs is forbidden. Depicting exhibitors name or logo in non flickering/non off-on type light is however permitted. Use of cloth banner inside and outside the Stand is not allowed. Suspending of display items from the Hall ceiling within the stands is also not permitted.

All raw space stands should make provision for a one meter ramp for physically challenged persons.

For Mezzanine Floor Stands, the following important points to be followed: Construction of Mezzanine floor stand shall be allowed only after submission of a structural and fire safety certificate from a registered Structural Engineer. Total Area of Stand booked should be 80 sqms or more and area of the mezzanine floor should not exceed 40% of the ground area booked. Total Height of stand with mezzanine should not exceed 4.2 metres. The maximum permissible height below the mezzanine floor is 3mtr. Can be used only as a visitor hospitality lounge. Exhibits / display items will not be permitted on the mezzanine floor. The mezzanine floor should be equipped with at least one fire extinguisher. Offices / cabins with closed walls & ceilings are strictly prohibited on the mezzanine floor. The mezzanine floor must be an open area with safety railings of 1.2m height on open sides. Construction of mezzanine floor stand must be at least 1m away from the boundary of all open sides of the stand.

Exhibitors under raw space category must order and pay for electricity connection on the basis of their maximum demand of connected load in KW and 3 phase connection, before the mentioned deadline.

Exhibitors are advised to take insurance policy covering their machinery/exhibit, transit, their exhibition personnel, and third parties.

Contractor must obtain official worker's passes for hall entry during construction and break-down period. Workers below 18 years will not be permitted to enter the premises and undertake any work at the venue.

The contractor deposit will be refunded after the exhibition subject to completion of construction work as per deadline schedule, clearance of the site by the contractors and no damage or garbage being recorded by the Expo Centre management. Organisers reserve the right to deduct an actual and appropriate amount for damages to the hall structures / venue, if any, made by the contractor from the security deposit paid.

ATTENTION ALL EXHIBITORS AND CONTRACTORS!!!

Organisers vouch for a dust free and healthy environment during the stand build up days.



Use of prefabricated, pre-finished, ready to fix, modular stand building recommended.

Use this guideline for your stand design and building. Mail copy of this document to your stand contractor.
For any clarification, contact Event Managers, Unitech Exhibitions Pvt Ltd,
Ms. Reena +91 9500076535 or reena@unitechexpo.com